

[illegible]

9	• Distribution Cabinet 150kVA 600mm • The solution includes One (1) Distribution Cabinet(s) with the following features: • 600 mm- 24 INCHES Frame Size • No transformer Included • No Transformer • Input Voltage of 480V, 60Hz, 3 Phase, 3 wire plus ground • Output Voltage of 480V, 60Hz, 3 Phase, 3 wire plus ground • Cabinet Mounted Right Attached to Module with connecting cables factory supplied • No Input Breaker • Distribution • 2: 2x Sub feeds (30-250A) • 1: 175A: Sub feed One • 1: 175A:										
	Sub Feed Two										
10	• 80% Sub feed breaker rating • Monitoring • SNMP Communication • Front Access services design • Distribution Cabinet Startup is Included • Seismic Anchor Kits Included for Distribution										
	Compra e instalación de sistema de aire acondicionado de precisión de 8 toneladas para el cuarto del CT SCAN:										
11	Air Precision Machine for CT SCAN • Air- Cooled System- Up flow 8 Tons at 208V Air-Cooled System • Nominal 101 kBtuh (29.6 kW) at approximately 75 °F, 45% RG • 208 Voltage, 3 Phase, 60 Hz										
	System Details:										

12	•Øp follow with Front Air ☒Return •☺ontrol with High-Definition Display •Øsed communication •ØACnet IP (Ethernet Port) •ØNMP (Ethernet Port) •ØP Protocols over one network •Øvariable speed EC plug fans •Øigital scroll, variable capacity compressor utilizing R-410A •Ørankcase Heater •Øhermal Expansion Valve •Øompressor Sound Jacket •Øvaporator Type: titled- slab, cooper tubes- aluminum fins with hydrophilic coating •Øwo- Stage 12kW Electric Reheat. •Ønfrared									
13	☒Humidifier •Ø5,000 Amp, rms Short Circuit Current Rating Locking Disconnect Switch •Øual- float condensate pump factory- mounted internal to unit •Øilter Rating: MERV 9 per ASHRAE 52.2-2007 •Ønit color: RAL 7021 Black Gray Matte •Øupply Air Sensor •Øigh Temperature Sensor •Ømoke Sensor •Øompressor Overload Sensor •Øne Remote Shut Down Contact •Øhree Alarm Contacts •Ø4 Floor stand inch Floor stand •Øischarge Grille Plenum •Ø- Grille Plenum •Ølenum Color: RAL 7021 Black Gray Matte									
14	☒MICROCHANNEL REMOTE Heat Rejection System 230V ☒Air-Cooled Microchannel Condenser(s) using input supply voltage of 208/230 Volt 3 Phase 60Hz. ☒The air-cooled condenser featuring an all-aluminum microchannel coil and a variable speed fan motors on every fan. ☒The unit should be quiet and corrosion resistant. All electrical connections and controls are enclosed in a factory mounted NEMA 3R electrical panel. Cooper pipe connections are provided for brazing of field piping and connections are located next to the electrical panel.									
	Condenser Details:									

Tabla de Ofertar
Subasta Formal SUB-2022-2023-013-HURRA

Compra e Instalacion de Equipo de Tomografia computarizada (CT SCAN) y Acondicionamiento del cuarto del Hospital Universitario Ramon Ruiz Arnanau (HURRA) en Bayamon.

	It should be capable of performing all the necessary functions of a precision air conditioner including cooling, humidification, dehumidification, air filtration, and condensate management.										
--	---	--	--	--	--	--	--	--	--	--	--

*Nota:

Precio Total: _____

Nombre del Licitador: _____ Firma del Licitador: _____